

NOTICE
2022 Scott Township Roadway Improvement Program

Please read this alert carefully so you will know what to expect. Then if you have questions call the municipal engineer at 412-264-4400 or the Scott Township Director of Public Services at 412/276-5300. Our contractor, Youngblood Paving Inc., will be roto milling and resurfacing the streets listed below.

The following roads will be milled and resurfaced between Mid-August through Mid-September 2022.

Street	From	To	Length (LF)	Scope of Work
Brookfield Rd	Rockhill Rd	Rockfield Rd	1,050	Mill and Pave
Spring Valley Rd	Elmbrook Ln	Brookfield Rd	310	Mill and Pave
Woodcliffe Circ	Elmbrook Ln	Spring Valley Rd	1,080	Mill and Pave
Great Oak Dr	House # 1418	Township Line	1,065	Mill and Pave
Greenbriar Dr	Greentree Rd	Greentree Rd	2,025	Mill and Pave
Shady Knoll Dr	Wise Rd	Spreading Oak Dr	565	Mill and Pave
Gregg St	Kern St	Boland Way	315	Mill and Pave
Borland Rd	House #1800	Vanadium Rd	500	Mill and Pave

Weather permitting the contractor will spend four days milling asphalt from the streets listed above. Roto milling will only take a few hours to complete. However, at least one traffic lane on affected streets will be closed to vehicular traffic until the roto milling process is completed. The asphalt material removed during roto milling will be swept from the roadway surface and the road will be reopened to vehicular traffic. After roto milling, the road surfaces will be rough, and some areas will require repairs to the road base before a binder or wearing coat of asphalt can be applied. Care will be taken to apply temporary asphalt lifts in front of some driveways to allow vehicles to enter without scraping. Temporary asphalt will also be placed around manholes and utility boxes in the street. Weather permitting the binder or wearing course will be applied to the asphalt surface a few days after the end of the roto milling process. During this process, the affected traffic lane of the roadways will be closed to vehicular traffic for several hours. The contractor's activities will not interfere with regularly scheduled trash pickup. The contractor will be responsible for restoring any damage done along the township right-of-way during the paving process. Shortly after the completion of paving, lane lines (if required) and stop bars (if required) will be reapplied to the asphalt surface of the roadway.